BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/15/2021-22 Dated: 15-12-2021

APPROVED TENDER SCHEDULE –'B'

Item 07

Name of Work :-Repairs and Maintenance of foot path in ward No 03 of Yelahanka Satellite Town Sub Division.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri.P.RAVICHANDRA	
				Rate	Rate in Words
1	Removing and refixing stone slabs of drains and pointing in CM (1:3) as per the direction of Engineer in charge	Sqm	329.40	97.94	NinetySeven Paise NinetyFour Only
2	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (P.No-143 &136 ,I No-19.1&17.4& 17.1 of PWD BCSR 2018-19) 8km lead= 57+2.0x1.28x8 =77.48, including the cost of loading and unloading, disposal using private vehicle and lead off of 8km	Cum	218.00	189.45	One Hundred EightyNine Paise FourtyFive Only
3	Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 6.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143 of PWD BCSR 2018-19) , 8km lead= 2.0x1.28x8 =20.48 , including the cost of loading and unloading, disposal using private vehicle and lead off of 6km	Cum	2371.80	56.27	FiftySix Paise TwentySeven Only
4	Providing and laying in position plain cement concrete of Mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	18.00	5550.29	Five Thousand Five Hundred Fifty Paise TwentyNine Only
5	Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications	Sqm	194.80	982.24	Nine Hundred EightyTwo Paise TwentyFour Only

	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	29.22	1761.13	One Thousand Seven Hundred SixtyOne Paise Thirteen Only
7	Providing and laying 100mm thick pre-cast cover slabs over drains of width not exceeding 800 mm using M20 concrete reinforced with steel @ 6.00 kg/Sqm, slabs jointed in CM 1:3 proportion and nicely finished including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, HOM of machineries, curing, lead and lift charges etc, Complete as per MORTH specifications No. 1500, 1700.	Sqm	354.60	1691.36	One Thousand Six Hundred NinetyOne Paise ThirtySix Only
8	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete.	Nos	1100.00	383.46	Three Hundred EightyThree Paise FourtySix Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.